## Gebäudebetrieb

archetype name	NFA in m <sup>2</sup>	energy carrier template	existing building final energy heating in kWh/m²a	existing building final energy hot water in kWh/m²a	Bestand Endenergie in kWh/m²a	Außenwandsanierung Endenergie in kWh/m²a	Dachsanierung Endenergie in kWh/m²a	Fenstersanierung Endenergie in kWh/m²a	Komplettsanierung Endenergie in kWh/m²a
A	147.63	Strom-Wärmepumpe Sole-Wasser (0/35)	60.5	20	80,50	76,86	78,54	74,70	68,44
В	162.3	Strom-Wärmepumpe Sole-Wasser (0/35)	60.5	20	80,50	76,86	78,54	74,70	68,44
С	139.13	Strom-Wärmepumpe Sole-Wasser (0/35)	60.5	20	80,50	76,86	78,54	74,70	68,44
D	164.41	Strom-Wärmepumpe Sole-Wasser (0/35)	60.5	20	80,50	76,86	78,54	74,70	68,44